

ConCribē



Shear resistance test  
Flashjoint  
150 mm

# ConCribes



|               |                               |
|---------------|-------------------------------|
| Reference     | kf20210409                    |
| Project name  | SHEAR TEST FLASH JOINT 150 MM |
| Date          | 2020.03.24                    |
| Contact       | TOFTEGAARD BYG                |
| Designed by   | ABO                           |
| Verified by   | AFO                           |
| Customer name | TOFTEGAARD BYG / FLASH JOINT  |


## Scope

The purpose of the test is to document the shear resistance of flashjoint 150 mm in a concrete joint in a 150 mm thick concrete beam.


The test is designed as beams of 400 mm length and 100 mm width, with thickness 150 mm to be tested according to EN 12504-3 for pull off resistance.

The beams are produced at a precast plant using C20/25 concrete to demonstrate the lowest possible performance at low concrete grade. Concrete is certified to EN 206.

## Flashjoint profile




# ConCribes



Design of the test beams and location of the flashjoint 100 and 150.

NOTE: THICKNESS OF THE CONCRETE BEAMS IS 100 MM INSTEAD OF 150 MM

# ConCribes



## Test set up

Each beam is placed one at a time on the test bench against the above test sketch. One part of the beam across the flashjoint is fully supported along its length so movement in y direction is restrained entirely. The other part is only supported at end so it's free to move in y direction when pressure on this part close to the joint increases.

# ConCribes



## Test equipment

20 tons bench with hydraulic indicator



The bench is certified to :

| Directive/Regulation | Harmonised standard   |
|----------------------|---|
| 2006/42/EC           | EN 1494:2000+A1:2008<br>EN ISO 12100:2010<br>EN ISO 13857:2008<br>EN 349:1993+A1:2008 |

# ConCribе



## Test set up

### *Beams*

The beams were poured on 17-03-21, 18-03-21 and 19-03-21  
They were demolded at 12 hours and stocked into 20 degrees hot water for 23 days.  
Test was performed on 09-04-2021



Flashjoint 150 beam

# ConCribе



Test report

FJ150 17-3-21





# ConCribes



First crack at 2 tons  
Collapse at 3.5 tons



# ConCribes



FJ150 18-03-21



First crack at 1.5 tons  
Collapse at 2.5 tons

ConCribе





# ConCribes



FJ15019-3-21



# ConCribes



First crack at 2.5 tons  
Collapse at 3.5 tons



# ConCribе



## Test conclusions

|    |   |                                      |
|----|---|--------------------------------------|
| Ø  | Diameter of the cylinder                    | 45 mm                                |
| A  | Area cylinder                               | 1590 mm <sup>2</sup>                 |
| Ac | concrete section area                       | 15000 mm <sup>2</sup> (100 x 150 mm) |
| Po | Pressure at first crack                     |                                      |
| P1 | Pressure at collapse                        |                                      |
| Fo | Force at first crack Mpa                    |                                      |
| F1 | Force at collapse Mpa                       |                                      |
| Ro | Shear resistance Mpa                        |                                      |
| R1 | Shear resistance Mpa                        |                                      |
| Rs | Shear resistance at SLS of FJ 150 per meter |                                      |
| Ru | Shear resistance at ULS of FJ 150 per meter |                                      |
| Vc | shear capacity concrete                     | Vc=0.34 Mpa for 30 Mpa concrete.     |

| FJ 150  | Po t | P1 t | Fo Mpa | F1 Mpa | Ro Mpa | R1 Mpa | Rs        | Ru         |
|---------|------|------|--------|--------|--------|--------|-----------|------------|
| 17-mars | 0,5  | 1    | 0,31   | 0,62   | -0,03  | 0,28   |           |            |
| 18-mars | 1    | 2    | 0,62   | 1,23   | 0,28   | 0,89   | 41,5 kN/m | 133,9 kN/m |
| 19-mars | 1,5  | 2,5  | 0,92   | 1,54   | 0,58   | 1,20   | 87,7 kN/m | 180,1 kN/m |
| Average | 1.25 |      |        |        |        |        | 64,6 kN/m |            |

\*operator error at testing: load was applied eccentrically

## Test expectations


| Flashjoint | LTE                 |
|------------|---------------------|
| 150        | 100 % up to 64 kN/m |

# ConCribes



## Model without FJ

|           |                                       |             |
|-----------|---------------------------------------|-------------|
| Thickness | 150 mm                                |             |
| Subgrade  | 5 N/cm <sup>3</sup> *                 | *min. value |
| HGV       | 44 t – wheel load 21 kN unfactored ** | ** assumed  |




Shear force in the joint : 121.94 kN/m

# ConCribе



## Model with FJ

|                      |                                       |             |
|----------------------|---------------------------------------|-------------|
| Thickness            | 150 mm                                |             |
| Subgrade             | 5 N/cm <sup>3</sup> *                 | *min. value |
| HGV                  | 44 t – wheel load 21 kN unfactored ** | ** assumed  |
| Elastic support (FJ) | 64 kN/m                               |             |



## Conclusion model

| FJ 150 | Without FJ kN/m | With FJ kN/m | Value of shear resistance FJ |
|--------|-----------------|--------------|------------------------------|
| Shear  | 121.94 kN/m     | 60.21        | 61.73 kN/m                   |



# ConCribes



## Test conclusion

The tested shear resistance of Flashjoint 150 has shown **64 kN/m at SLS**. It is to be noted that the beam was NOT supported as it was calculated to be in the expected test calculation.

The modelled test resistance has shown 61.73 kN/m for a 44 t HGV on 5 axles at SLS.

Test was also performed on 2 beam only, therefore considering potential variation's coefficient.  
The first beam failed due to operator error.

Since CS TR34 does consider the use of dowels to reduce load transfer by 30 %, the use of FlashJoint is indeed a valid alternative to dowels and bars, as it conservatively reduces load transfer with **49%**.

Test was performed with plain concrete, FRC would improve results in any case.